

Tender No-005, dated- 12.11.2024.

**TENDER NOTICE**

**Sealed quotations are invited from reputed and experienced firms as per following details.**

1. Name of work : Uplift of Yajnashala Campus of the school
2. Estimated Area : 6689.43 Sq. ft.
3. Time of Completion : Within 15 days from the date of approval
4. Date of Tender Notification : 12/11/2024
5. Last Date/Time for Receipt of Bids : 16/11/2024
6. Name and address of office inviting Tender : D.A.V. Public School, BSEB Colony, Patna-23
7. Contact No. of procurement office : School's Telephone No. 0612-2283467

**FOLLOWING POINTS NEED ATTENTION**

1. Only the quality materials (Branded Company) and standard workmanship will be acceptable.
2. Each interested firm will submit the two sealed quotations viz financial bid and technical bid.
3. The school shall not be liable to pay any tax, freight etc. which has not been expressly stipulated in the quotation in the event of acceptance of the quotation. The school will deduct TDS as per rules of Income Tax.
4. The undersigned does not bind himself/herself to accept the lowest quotation and reserves the right to accept the quotation in whole or in part i.e., with respect to all the articles mentioned in the attached statement or in respect of one or more than one articles specified on the attached statement as he/she may decide.
5. On acceptance of the quotation it will become a contract and the contractor shall be bonded by the terms and conditions of the quotation as well as contractor must fulfil the terms and conditions of Government of India/Bihar.
6. The quantity of articles indicated in the attached statement may be increased or decreased at the discretion of the undersigned without assigning any reason.
7. In the event of acceptance of quotation and placing of the order for repairing the articles ordered for, would be subjected to an inspection by the undersigned or architect and are liable to be rejected if the articles supplied are not according to approved samples or do not confirm to the specifications prescribed by the architect.
8. The rate quoted by the contractor shall hold good up to finishing of the construction. No amendment will be expected in the approved rate.
9. The payment will be made to the contractor through A/c payee cheque as per the agreement and duly approved by the architect.
10. Quotations which do not comply with the above conditions are liable to be rejected.
11. The site and proposed map is open for inspection before bidding for all interested persons.
12. All due formalities related to safety and security of the labourers (as per Govt. Norms) is sole responsibility of the firm who will accept the work.
13. Management of wastage will be responsibility of selected firm and the expenses incurred over it will be beared by the selected firm.
14. Please add- the undersigned may change the dates as well cancel the tender at any time without any prior notice.
15. All disputes subject to Patna Jurisdiction only.

**MEMBER OF BUILDING SUB-COMMITTEE**

1. Mr. Ram Anugrah Narayan Singh, LMC Chairman
2. Mrs. P. Sofat, LMC Vice-Chairman
3. Mr. S.K.Jha , Regional Officer -cum- Manager , DAV Public Schools, Bihar Zone-A
4. Mr. A. C. Jha, Principal, DAV Public School, BSEB Colony, New Punaichak, Patna.
5. Mrs. Jyoti Sinha , Principal, DAV Public School, Walmi Complex, Phulwarisharif, Patna
6. Mr. Vijay Kumar Pathak, Principal, Dr. G.L. Dutta DAV Public School, Kankarbagh, Patna
7. Teacher members.



A. C. Jha  
Principal

Principal

D. A. V. Public School

B.S.E.B. Colony, New Punaichak, Patna-23  
Aff. No.-330050 School Code-8.

  
S.K. Jha

Regional Officer-cum-Manager

Manager

D. A. V. Public School

B.S.E.B. Colony, New Punaichak, Patna-23  
Aff. No.-330050, School Code-85046

**FOR TECHNICAL APPROVAL**

<b>ABSTRACT OF CONSTRUCTION COST OF UPLIFT OF YAZSHALA CAMPUS OF D.A.V. PUBLIC SCHOOL,</b>						
<b>B.S.E.B. COLONY, NEW PUNAICHAK, PATNA, BIHAR</b>						
<b>Sl.No.</b>	<b>S.O.R.</b>	<b>DESCRIPTION</b>	<b>Qty.</b>	<b>Unit.</b>	<b>Rate</b>	<b>Amount</b>
<b>(1) UPLIFT OF YAZSHALA CAMPUS</b>						
Area of Yazshala campus = 6689.43 Sft. (621.69 Sqm)						
<b>SECTION-I (EARTH WORK)</b>						
1		Earth wok in excavation in foundation trenches or drains (not exceeding 1.5 M. in width or 10 sqm. on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 M including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50M.				
		All kinds of soil.	10.60	Cum.		
<b>SECTION-II (DRAINAGE WORK)</b>						
2		Constructing brick masonry road gully chamber 45x45x77.5 cm with bricks in cement mortar 1:4(1 cement: 4 coarse sand) with precast R.C.C. Vertical grating complete as per standard design:				
		With common burnt clay F.P.S.(non modular) bricks of class designation 7.5		5 Each		
3		Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete:				
		250 mm dia R.C.C. pipe	29.88	metre		
4		Making connection of drain or sewer line with existing manhole including breaking into and making good the walls,floors with cement concrete 1:2:4 mix(1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size) cement plastered on both sides with cement mortar 1:3 (1 cement: 3 coarse sand), finished with a floating coat of neat cement and making necessary channels for the drain etc. complete:				
		For pipes 100 to 250 mm diameter		2 Each		
<b>SECTION-III (SAND FILLING)</b>						
5		Supplying and filling in plinth with local sand and under floors including watering, ramming, consolidating and dressing complete.				
			142.48	Cum		
<b>SECTION-IV (PAVER WORK)</b>						
<b>Sl.No.</b>	<b>S.O.R.</b>	<b>DESCRIPTION</b>	<b>Qty.</b>	<b>Unit.</b>	<b>Rate</b>	<b>Amount</b>

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
6		Providing and laying factory made coloured chamfered edge cement concrete paver blocks of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. complete as per manufacturer's specifications & direction of Engineer-in-Charge. 60mm thick C.C. paver block of M-35 grade with approved colour, design & pattern.	467.30	Sqm		
		<b>SECTION-V (R.C.C. /P.C.C. WORK)</b>				
7		Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering- all work upto plinth level.				
		1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size.)	2.27	Cum.		
		<b>SECTION - VI (STAINLESS STEEL WORK)</b>				
8		Providing and fixing stainless steel (Grade 304 ) railing made of Hollow tubes, channels, plates etc. including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i.e. fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc. of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	276	Kg		
		<b>SECTION - VII (MASONRY WORK)</b>				
9		Half brick masonry with bricks of class designation 100A in foundations and plinth in:				
		Cement mortar 1:4 (1 cement: 4 coarse sand)	2.32	Sqm		
		<b>SECTION - VIII (FLOORING WORK)</b>				
10		Marble stone flooring with 18mm thick marble stone ( sample of marble shall be approved by engineer in charge) over 20mm thick bases of cement mortar 1:4(1 cement, 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing complete with.				

Sl.No.	S.O.R.	DESCRIPTION	Qty.	Unit.	Rate	Amount
		Rajnagar plain white marble 18mm thick above 0.20 sqm up to 0.50 sqm.	2.63	Sqm		
11		Providing and fixing first quality ceramic glazed wall tiles confirming to IS 15622(Thickness to be specified by manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by engineer in charge in skirting, risers of steps and dados over 12mm thick bed of cement mortar 1:3 (1 cement, 3 coarse sand) and jointed with grey cement slurry @ 3.3 Kg/sqm including pointing in white cement mixed with pigment of matching shade complete.	66.88	Sqm		
		<b>SECTION-IX (PLASTER WORK)</b>				
12		12 mm cement plaster in coarse sand of mix: 1:6 (1 cement; 6 coarse sand).	42.27	Sqm		
13		15 mm cement plaster on rough side of single or half brick wall of mix 1:6 (1 cement; 6 coarse sand).	22.32	Sqm		
		<b>SECTION- X ( FINISHING WORK)</b>				
14		Distempering with 1st quality acrylic distemper, having VOC(Volatile Organic Compound) content less than 50 grams/litre, of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour				
		Two coats	161.96	Sqm		
15		Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:				
		Old work (Two or more coat applied @ 1.43 ltr/10 sqm over existing paint surface.	325.43	Sqm		
16		Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete.	325.43	Sqm		
		<b>SECTION- XI (MISCELLANEOUS WORK)</b>				
17		For cleaning of rubbish, up rooting shrubs, dismantling work, leveling, Plaster repair and disposal of materials to the dumping ground etc. complete.	LS			
		TOTAL				
		FOUNDING OFF				

Note:- Painting of security room from out side, compound wall of yazshala campus from inside and yazshala from inside & outside will be done.